



May 18, 2021

Subject: Montague County Jail, TX – Video Surveillance System Upgrade

**Scope of Work**

MTS will provide and install thirty-nine new (39) Pelco IMP231-1ERS 2MP cameras. MTS will provide and pull new Cat6 cable to each new IP camera. Existing cameras will remain as is and will be added to the new recorders. A total of 77 cameras (39-new, 38 existing) will be recorded on the new recorders.

MTS will provide and install two (2) Pelco VXP-P2-96-6-D 96TB servers to replace the existing Pelco Digital Sentry system. This will allow storage of recordings for up to 30 days at 30FPS with a 50% activity rate.

MTS will provide and install one (1) viewing stations to replace existing viewing stations. MTS will reuse existing 55" monitors as is. A new 1000w Eaton UPS will be supplied with this computer.

MTS will provide one (1) new HP 2930F-48G-PoE network switch to accommodate new IP cameras listed above. The new network switch will be mounted in the existing rack.

MTS will reuse all existing field devices and cabling as is except where otherwise noted. MTS will assist the facility in troubleshooting problems with existing field devices. Once an existing field device is found to be defective, it will be the facility's responsibility to repair or replace the existing device.

**Pricing Total**

MTS is pleased to provide the above scope of work for a total of **\$93,615.00**.

**Pricing Breakout**

**Material- \$66,488.82**

**Labor-\$27,126.18**

**Texas Buy Board Vendor Number-**

# **MTS**

**Montgomery  
Technology  
Systems, LLC**

## **Warranty**

1. MTS provides the manufacturers standard warranty that all products are to be free of defects in material and workmanship for a period of one (1) year from date of substantial completion.
2. Conditions of the warranty apply only to materials supplied as part of this quote.
3. MTS is not responsible for damage caused by neglect or abuse by others who have gained access to the equipment.

## **Lead Times and Submittals**

1. MTS will provide submittals within twelve (12) weeks of receipt of contract or purchase order.
2. Upon receipt of approved submittals and first payment, MTS will order all material and schedule the installation of the project. Material lead times are eight (8) weeks. However, material lead times can be affected by forces outside of MTS' control (i.e., material shortages). If the material lead times are longer than stated, MTS will advise at the time the material is ordered.
3. MTS will complete the installation within eight (8) weeks of material arriving onsite.

## **Terms of Payment**

1. All pricing is good for 30 days from date of quote.
2. MTS will invoice 50% of the project total once submittals have been approved. Material for the project will not be ordered until payment for this invoice has been received.
3. MTS will invoice the remaining 50% of the project total once the project has been completed as outlined in the scope of work section.
4. All invoices will be paid within 30 days from invoice date.
5. All invoices not paid within 30 days will be subject to a 1.5% per 30-day late charge.
6. All invoices not paid within 60 days will result in the account being put on credit hold. Once an account is placed on credit hold, MTS will discontinue all services until the account is restored to good standing.
7. If this project is sales tax exempt, a tax exemption certificate must be provided prior to material being ordered.

If I can be of any assistance or answer any questions, please do not hesitate to call me at 800-392-8292.

Sincerely,

**John Findley**

**[Johnf@montgomerytechnology.com](mailto:Johnf@montgomerytechnology.com)**

Montgomery Technology Systems LLC  
 23 Old Stage Rd.  
 Greenville, AL 36037

# Project Estimate

Proposal Date: 5/18/2021  
 Estimate # 0914

<b>Bill To:</b>
Montague County Jail Attn: Capt. Oakley P.O. Box 127 Montague, TX 76251

<b>Ship To</b>
Montague County Jail 111 S. Grand Montague, TX 76251

Terms	Net 30
-------	--------

Item	Description	Qty.	Rate	Total
IMP231-1ERS...	SARIX PRO 3 IR ENV DOME, 2MP	39	450.2941	17,561.47T
IMP3PM-1E-NI	SARIX PRO 3 DOME PENDANT MOUNT	6	71.76	430.56T
SWM-SR-NI	Wall mounts light gray	6	41.86	251.16T
VXP-P2-96-6...	VXP 2nd Gen Power Series 96TB (12x8TB HDD) RAID6 Mirrored OS	2	13,574.60	27,149.20T
VXP-1C-3Y-NI	VXP 1CH WITH 3YR SUP LICENSE	77	118.40403	9,117.11T
91305-NI	HP Computer w/ Window 10 (Pelco Viewing)	1	1,314.30	1,314.30T
9PX1000RT-NI	Eaton 1000W Rack Mount	1	781.77	781.77T
DP2HDMM3M...	StarTech, Display port to HDMI 10' cable	2	29.51	59.02T
6P4P24-BL-P...	LANmark Plenum Cat6 Cable (Blue) (10136226010)	10,000	0.2758	2,758.00T
HC6B03-NI	Hubbell Cat6 3' Blue	50	6.78	339.00T
49255-H48-NI	Leviton 1RU 48 port Flat Quickport Patch Panel, will use Atlas X1 Jack	1	54.96	54.96T
61UJK-RL6-NI	Atlas-X1 Cat6 UTP Jack (Blue)	48	9.165	439.92T
Parts-NI	Connectors, Fasteners, Misc. Parts, etc.	1	1,950.00	1,950.00T
JL557A-NI	Aruba 2930F 48G 4SFP switch - PoE+ with 740W power supply	1	4,302.35	4,302.35T
Project Manag...	Project Management	1	8,000.00	8,000.00T
INSTALL LAB...	Labor for installing parts	240	50.00	12,000.00T
Expenses	Expenses (Hotel, Airfare, Rentals, etc.)	1	5,000.00	5,000.00T
SHIPPING	SHIPPING	1	926.18	926.18T
Licenses and ...	Licenses and Permits	1	1,200.00	1,200.00T
	Sales Tax		0.00%	0.00
<b>Total</b>				<b>\$93,615.00</b>